

# Tower and Bridge Breaker

The bridge is placed to span two tables. A block with hooks is used to evenly distribute the load. Weights (2.5 pounds each) are added to the sling one at a time until the structure is compromised.

